WP1: Construction logistics scenarios and stakeholder involvement

Deliverable 1.2: Application of scenarios of construction logistics

October 2021



Document change record			
Version	Date	Status	Modified by
0.1	21.9.2021	Case studies from Belgium	Nicolas Brusselae, VUB
0.1	27.9.2021	Case studies from Sweden	Anna Fredriksson and Mats Janné, LiU
0.1	8.10.2021	Case studies from Norway, 1 st version of D1.2 based on inputs from Belgium, Norway and Sweden	Selamawit Mamo Fufa, SINTEF
1	13.10.2021	Final version	Anna Fredriksson, LiU

MIMIC Deliverable 2.1

Version: 1.0

Date: 20211013

Responsible partner: LiU+SINTEF

Authors: Anna Fredriksson, Linköping University, Mats Janné, Linköping University, Selamawit Mamo Fufa, Sintef, Christoffer Venås, Omsorgsbygg, Nicolas Brusselaers, Vrije Universiteit Brussel

Contributors: Koen Mommens, Vrije Universiteit Brussel



Table of contents

TABLE OF CONTENTS	IV
1. INTRODUCTION	1
2. CASE STUDIES FROM BELGIUM	2
3. CASE STUDIES FROM NORWAY	5
4. CASE STUDIES FROM SWEDEN	9
ACKNOWLEDGEMENTS	19

1. Introduction

The purpose of MIMIC - Minimizing impact of construction material flows in cities: Innovation cocreation project is to demonstrate how Smart Governance concepts can be used as an aid in the construction and city planning processes to facilitate and support logistics to, from and on urban construction sites to improve mobility and reduce congestion within cities and thereby reduce the negative impact of construction sites on the surrounding community.

The MIMIC project integrates research within construction logistics, construction management, city logistics, sustainability, and optimization of flows, with the goal of developing the Smart Governance Concept 2.0. This concept provides the implementation partners (Cities and companies in the construction process and supply chain) with a structure of tools organized into a supportive platform for construction logistics issues in the urban development decision and procurement processes (D4.2 and D4.3). The tools help to increase the knowledge of construction logistics (D1.3), collecting stakeholder needs and criteria of construction logistics scenarios (D1.1, D1.2 and D1.4), and to evaluate the impact of construction logistics solutions on different stakeholders (D2.2, D2.3, D3.1, D3.2 and D3.3).

This deliverable D1.2 Evaluations of construction logistics scenarios at implementation partners is part of WP1 Construction logistics scenarios and stakeholder involvement in the MIMIC project. The aim of D1.2 is to provide a catalogue of case studies from Belgium, Sweden and Norway (Tabel 1), each providing an insight to construction logistics activities, impacts and learnings.

Tabel 1. List of case studies			
Country	Case study		
Belgium	Brussels Construction Consolidation Centre (BCCC)		
	City Campus Anderlecht		
	Lia nursery school (Lia barnehage)		
Norway	Olav Vs Street (Olav Vs gate)		
Norway	Oslo emergency ward (Oslo storbylegevakt)		
	Tåsen nursing home (Tåsenhjemmet)		
Sweden	Stockholm Royal Seaport (SRS)		
	City of Uppsala		
	Älvstranden AB – Construction logistics strategy		
	Älvsborgs sjukhus (Borås)		
	Helsingborgs lasarett (Helsingborg)		

Tabel	1.	List	of	case	studies

2. Case studies from Belgium

Project	Brussels Construction Consolidation Centre (BCCC)
name	
	Figure. Brussels Construction Consolidation Centre with deliveries of construction materials by barge at the Port of Brussels. Illustration: Shiplt © 2020.
Project	The Brussels Construction Consolidation Centre aims to provide Brussels
type, size	construction sites with a logistical platform for the consolidation of material
and time	deliveries. This project aims to test the operation of such a construction
frame	consolidation centre, but also its digital solution, while measuring the societal
	impacts. The BCCC has been operational since the end of 2019 and experiments
	have been conducted with different partners such as material suppliers and
Dustant	contractors.
Project	The BCCC is located at the Port of Brussels (Belgium), hence offering
location	transhipment possibilities and construction material deliveries through the inland waterways arriving at the heart of Brussels. From there, the last mile is covered
	by HDV in a consolidated and optimized way.
Constructi	The experimentation of the consolidation centre initially focused on the transport
on logistics	of palletizable materials (concrete blocks, insulation, facade bricks, bags of
	plates, etc.). Although the focus was initially on supplying large construction sites in the Brussels Region, the practice highlighted the multitude of situations to which the BCCC was able to respond. First, in terms of clients, this type of solution could be just as relevant for material suppliers (to improve their services), for construction companies (to set up specific logistics for one or more sites) and for real estate developers (e.g. to facilitate the reuse of materials). From an operational point of view, a whole series of experiments could then be tested: deliveries to large building sites; consolidated deliveries to several large sites; deliveries to infrastructure sites; deliveries of prefabricated elements; provision of storage space managed by a company itself; reverse logistics, remassification and material re-use; deliveries to smaller sites using vans and/or cargo bikes; etc.
Impact and	In just over a year, 21 barges have come to supply the centre with various
learnings	materials, each barge corresponding to 50 fewer lorries on the roads. The BCCC
	shows that the modal shift from road to inland waterway transport significantly
	reduces overall transport external costs. The environmental costs that could be avoided by using alternative modes of transport, taking trucks from the road and
	avoiding half-empty trucks delivering to site, are obvious if the manufacturing
	company is located close to the waterway. It is worth pointing out that this last
	condition restricts IWT of construction materials to companies who are initially

located close to an inland waterway axis. Also, its end destination (i.e., the construction site) should be located close to a transhipment point (such as a CCC), allowing to reduce overall costs and generating enough volume to be bundled on barge (for neighbouring construction sites). It is thus not always feasible to ship (all types of) materials through water. Although trucks are still top of mind in Belgium, initiatives guide construction sites in identifying suppliers close to waterways, and how to include clauses into tender documents and asking for options for environment-friendly solutions. In this way, these services aim to provide a transparent view on (a) the total logistics cost and (b) the service levels of using the waterways. The construction logistics decision-making, comparing different logistics solutions and taking into consideration all points of view, should be conducted in order to evaluate both the cost perspective and the added value services that e.g., a CCC can provide, as to highlight potential benefits and drawbacks to construction sites and the different actor groups.

Project	City Campus Anderlecht		
name			
	Figure. City Campus construction site simulation. Illustration: Van Roey Vastgoed © 2019.		
Project	The pilot site is the mixed 'City Campus' project, which will ultimately result in a		
type, size	17,600 m ² site for an SME park for agri-food companies and social and student		
and time	residences.		
frame			
Project	Anderlecht (Brussels), Belgium. The site is located within the Brussels Outer		
location	Ring (R0) and the BCR and is considered as a typical 'large' construction project in Brussels, with a strong output value upon completion. The municipality in which the site is located, has a population density of 6,394.34 inhabitants/km ² and a total population of 108,940 inhabitants. The location offers a variety of relevant and potential transport accessibility entries and exits: the area is in proximity of major road axes such as the R0 ring of Brussels and the E19 highway as well as the main navigable inland waterway axes of the Brussels- Charleroi Canal and the Willebroekse Vaart. The neighbourhood offers a rich diversity in vicinal stakeholders, including a shopping centre, a higher-education college and various local businesses. The construction traffic have a dedicated entrance and exits through the site, through which the vehicles can unload materials on an on-site delivery way. Each work and unloading space opens onto the public square and is accessible to freight traffic along a courtyard that is largely covered with a noise-reducing porch in order to limit the inconvenience for the surrounding houses.		
Constructi	'City Campus' is organized in association with the public-private partnership		
on	between owner and city development agency CityDev and main building		
logistics	contractor Van Roey Vastgoed.		
Impact	Construction logistics analyses are be based on OBU (on-board unit) data of		
and	+3,5 T trucks, providing a better understanding on the amount and type of flows		
learnings	generated in practice by construction works, and toquantify the impact of these flows on urban sustainability. This allowed to assess the impact on economic, social and environmental sustainability (with specific focus on congestion, emissions and safety) of construction freight flows from origin to destination. This analysis also allowed for the development of a collaborative Stakeholder Framework for construction logistics.		

3. Case studies from Norway


Project	Lia nursery school (Lia barnehage)
name	
Project type,	Lia nursery school, with a total heated floor area of 1600 m ² . It is the first
size and ambition	fossil free nursery school in Norway and certified as BREEAM very good.
Time frame	Construction period from April 2016 - November 2017
Project	Harald Sohlbergs vei 19, Oslo, Norway
location	
Construction logistics	The construction logistic was planned in the early project phase. The location of the construction site, which was next to school and it's urban setting with lack of storage, leads to detail planning of deliveries and logistics to, within and from construction site. Use of prefabricated solutions (for walls, floors, and ceilings) and locally sourced elements (concrete) were considered to reduce construction period, transport frequency and associated waste and emissions.
Impact and learnings	More time and resources spent in the early planning phase, environmental requirements or targets included in the early procurement process and close dialogue with actors involved throughout the project period enabled to achieve the project ambitions. Lack of electric machineries at the time and other unforeseen challenges, such as machineries delivered with tank filled by diesel even if it was planned to use biodiesel, pointed out the importance of sharing knowledge and experience and considering external factors in the early planning phase.

Project	Olav Vs Street (Olav Vs gate)
name	
Project type,	Figure. Olav Vs Street construction site. Illustration: SINTEF © 2019. Olav Vs Street is the first emission free construction site in Norway. It is 180m
size and	long pedestrian street upgrading project aiming to create a new city space
ambition	with no traffic. The upper section of the street was transformed to pedestrian
	street by moving the taxi stand. The street is widened in the lower section by
	replacing parking spaces with good delivery bays and disability parking and
	leaving the remaining space for relocated taxi stand with charging stations for electric taxis.
Time frame	September 2019 - December 2020
Project	Oslo city centre
location	
Constructio	The project started with a dialogue with manufacturers and suppliers of
n logistics	machineries and equipment on available electric construction machinery
	and local grid operators to ensure sufficient power supply to construction
	site. There have been limited electric machineries available at the time. The
	project entered an agreement with rental service to secure supply of electric
Impact and	machineries. Use of electric construction machineries was estimated to enable saving 35
learnings	000 litres of diesel and 92500 kgCO ₂ eq. The construction site also
isarings	facilitated noise reduction which contributed to improved health and safety
	of the workers. The city of Oslo plays major role by challenging the market
	on providing emission free solutions and also support the process by
	providing free electricity during the construction period. Early planning and
	good dialogue with market on available emission free technologies and
	infrastructure enable to realise emission free construction site. The lesson
	from the project also shows the need for training of construction workers on
	use of new emission free technologies.

Project	Oslo emergency ward (Oslo storbylegevakt)			
name	Figure. Olav Vs Street construction site. Illustration: Oslo Munucipality			
Project type,	The new emergency ward is an on-going project with a total area of 25			
size and	000m ² . The project aimed to fulfil passive house standard and to be certified			
ambition	with BREEAM excellent.			
Time frame	Demolition in 2019, construction 2020-2023			
Project	Trondheimsveien 235, Oslo, Norway			
location				
Construction	Digital scheduling, planning system for transports and (material) deliveries			
logistics	and time restrictions for intermediate storage on site (max. 14 days) is			
	considered. This means that progress of the construction is planned in 14			
	days intervals, and just-in-time deliveries as the main strategy. The use of			
	crane truck is paid directly by the subcontractors, penalizing such use of			
	internal transport, whilst incentivized direct delivery from the delivery			
	vehicle. Delivery vehicles has direct arrival from the highway with an own construction road to avoid traffic in the neighborhood, and deliveries are			
	time restricted (through the booking system). Almost 130 000 m^3 of			
	excavated mass has been transported from the site. Some had been			
	brought by barge as filling masses in the seaside, with Fjordbyen as a new			
	residential neighbourhood, thus avoiding app. 40 km of road transport.			
Impact and	Good planning of logistic activities and importance of electrification of			
learnings	construction process. With lots of mass transport, the choice of means of			
	transport has also significant impact. Choice of material, including use of			
	low carbon concrete and reuse of hollow concrete slab elements from from			
	the old, decommissioned Government Quarter, has been used in order to			
	reduce the carbon footprint of the building.			

Project	Tåsen nursing home (Tåsenhjemmet)
name	
Project type,	Figure. Tåsen nursing home. Illustration: Arkitema Arkitekter Tåsen nursing home for elderly is on-going four floor project with a total
size and	gross floor area of 14 500m ² for 135 residents and a day center for residents
ambition	and outside users. The project includes demolition of an existing nursing
	home and constructing a new one with an ambition to be the first energy
	plus house nursing home in cross-laminated timber in Norway. It is
	FutureBuilt model project and aimed to be certified as BREEAM
	outstanding.
Time frame	Construction period from 2021–2023
Project	Pastor Fangens vei 26 - 28, 0854 Oslo Nordre Aker, Oslo, Norway
location	
Construction	Selection of construction materials, use of prefabricated wood elements
logistics	such as cross laminated timber (CLT), is considered as a solution to
	reduce construction time, transport and on- site logistics need, and
	associated waste and GHG emissions. Possibilities of having large storage
	areas and coordination with material suppliers for just -in time deliveries
	with large vehicles, using full capacities and optimization packaging have
	been planned to be considered. All the masses from the demolition work
	are planned to be used in the project to reduce the mass transport.
	Walking and cycling routes, access to public transport and charging
	possibilities are also discussed to reduce transport intensity within the
	construction site. The project was on hold due to complaints from neighbors, prolonging the zoning process and affecting the size of the
	building and available green space around the nursing home.
Impact and	Fossil free as minimum requirements and use of emission free solutions
learnings	for construction site activities as award criteria in procurement procedure,
	and certification schemes such as BREEAM identified as main drivers to
	consider different measures. The project is a good example how public
	procurers take risk and push the limits to move away from traditional way
	of construction by setting ambitious but achievable requirements. The
	lesson from the project shows the need for involvement of citizens in the
	early planning phase of the project to avoid conflict of interest.


4. Case studies from Sweden



Impact and	Construction logistics is repeating the mistakes of its big brother, city logistics, in that it
learnings	has common utilization challenges and follows the same way of designing CLC setups
	based on implementation drivers. By showing that there is a difference between
	implementation and utilization drivers and challenges, the implementation often stems
	from a goal of reducing disturbances to third parties, whereas the drive for utilizing a setup
	stems from a need to increase efficiency on site and reduce unnecessary logistics
	activities. Construction projects can apply two possible strategies for utilizing a CLC.
	Either they use the CLC as a consolidation point to allow different suppliers' materials
	flows to be delivered as consolidated deliveries to the construction site, or they can use
	the CLC as an external storage point to facilitate JIT deliveries to site. Furthermore,
	projects that formulated a logistics strategy were found to utilize the CLC more as part of
	their operations than those that came into SRS without formulating a logistics strategy. It
	is thus important to note that, when starting a construction project in an urban
	development area that has a construction logistics setup, part of the planning for that
	construction project must be to develop a strategy for how to work with that construction
	logistics setup. Further reading, Janné and Fredriksson, 2021, Construction logistics in
	urban development projects - Learning from, or repeating, past mistakes of city logistics?,
	International Journal of Logistics Management.

Project	City of Uppsala
name	
	a second se
	Expressivice
	Figure. The CLS of Uppsala. Illustration: Catharina Danckwardt-Liljeström
Project type,	The city of Uppsala is to build and densify several areas within the coming
size and time frame	years. The areas are Rosendal, Ulleråker and Östra Sala Backe. To consolidate and control the flow to and from these areas, the city of Uppsala
	has procured a construction logistics setup (CLS).
Project	The projects the CLS is to serve are located in the central parts of Uppsala.
location	One of them are also close to the area from which the city gets its water.
Construction logistics	The goal with the CLS is to decrease the traffic through and within Uppsala and by this improve the living and working conditions in the areas. The CLS
10910100	should also help to decrease the construction time and the material waste.
	The CLS consists of a terminal on the outskirts of Uppsala close to the E6 and
	a booking calender. The terminal offers consolidation and short time storage.

	The city of Uppsala has provided a location for the terminal and procured a
	third-party logistics provider to run the terminal.
Impact and	The analysis showed that the municipality, the main contractors and the TPL
learnings	provider all found the consolidation effect to be positive. Though, the
	acceptance and success of the solution will depend on some actions being
	taken regarding both the construction logistics solution and its governance as
	well as what type of performance it is expected to deliver. A CLS cannot be
	designed only as a transport solution, it has to be seen as a part of the material
	flow to the construction sites and thereby more operations related
	performance measures have to be considered. It is also hard to get
	acceptance among politicians of the cost to run a CLS.



	storage, kitting, carrying, store on site, standardised etiquettes, follow up of
	performance and education.

Project	Älvsborgs sjukhus (Borås)
name	
	the second
	e e
	Figure Sädre Ähigheren Siulikus Illustration: Mate Jonné
Project type,	<i>Figure. Södra Älvsborgs Sjukhus. Illustration: Mats Janné</i> It is a 5-year project to build and renovate the psychiatric ward, the infection
size and	clinic, and the medical laboratory of the hospital in a medium-sized city in mid
time frame	Sweden.
Project	All three wards and clinics are operational during construction, with the current
location	medical laboratory scheduled for demolishing once the new laboratory is
	completed.
Construction	The main contractors site manager demanded a CLS to ensure that material
logistics	deliveries are running smoothly and in accordance with plans. The CLS is
	organizationally located under the main contractor and consists of a terminal,
	with additional services such as kitting, on-site materials handling, and a machine resource pool. Deliveries are carried out after call-offs, based on takt
	production. The main contractor has a dedicated logistics manager in the
	project, acting as the contact point between construction project and logistics
	provider. Terminal solution, ensure on-time deliveries and on-going operations
	on site, other services included are: on-site materials handling, Kitting,
	Machine resources, Routes within site and Education.
Impact and	The goal of utilising a CLS to include more than just avoiding disturbances.
learnings	The goal must also be to ensure that material deliveries and on-site logistics
	works within the hospital project and there is a continuous development
	process. First, there are many different stakeholders adding to the
	organizational complexity of the project. At the same time the structural
	complexity of operating a hospital while simultaneously building new parts or
	renovating it, means that there is also a big risk of physical disturbances within
	the hospital area. It is thus of utmost importance that any rules and regulations
	set by the CLS operator are adhered to and that the CLS operator has the
	mandate to enforce these rules. The CLS design must include measuring the

	overall performance of the CLS. The performance measuring must include the
	logistical efficiency of the solution, but also how well the CLS reduces
	disturbances and what the effect is on sustainability aspects.

Project	Helsingborgs lasarett (Helsingborg)
name	
	Order Contractor
	Booking and
	confirmation
	Waste and returns
	Delivery Checknoint Delivery
	Supplier Delivery Checkpoint Delivery allocation
	← Information flows
	← Material flows
Project type,	<i>Figure. The physical and information flows in the CLS setup. Illustration: Mats Janné</i> It is a 7-year project where the renovation of the main building is combined with
size and	the construction of new care buildings and parking garage. The hospital is
time frame	operational during the renovation and new-build project.
Project	The hospital is located in the middle of the city center adjacent to both
location Construction	residential, office, and school buildings. The regional council employed a construction management (CM) company to
logistics	manage the site and the material and resource deliveries. The goal of the
	logistics solution is primarily to reduce impact on third-parties and to ensure
	that the hospital operates as normal. As the hospital is located in the busy
	city center, the CM company opted for a checkpoint solution with a planning
	system for all delivery bookings and waiting area for lorries outside of the city. The CM company is managing the site as well as all delivery activities and by
	being part of the project management and having their own budget, they are
	in a position where they can focus on managing relationships and ensuring
	that all stakeholders strive towards a common goal, but they also have
	mandate to enforce rules and regulations towards contractors, suppliers, and
	transport providers in the project. However, as their mandate is only for the project, there has been issues in coordinating regional and local council road
	and construction works adjacent to the hospital project with what happens on
	site.
Impact and	The goal of utilising this CLS was primarily avoiding disturbances, i.e.,
learnings	ensuring that the hospital could be operational while the project was ongoing. This case shows that when introducing a CLS, it is important to consider
	This case shows that when introducing a CLS, it is important to consider where in the organizational hierarchy the CLS is located as this will signal
	actual and perceived mandate to enforce the regulations set for construction
	logistics within the construction project. Due to its position within the project
	organization and the dedicated own budget, the CM company had a
	comparatively easier journey to get all stakeholders onboard with the CLS. The main issues encountered in Helsingborg was that at the same time as
	the hospital project was running, the municipality had smaller infrastructure
	projects performed adjacent to this large-scale project and the access roads

of the site. Ideally, the municipality would have postponed their infrastructure
projects until the hospital project was completed. However, this is not always
a possibility as at times, urgent repair work needs to be undertaken in the
infrastructure. At these times, the CLS should be consulted to allow for
discrepancies in access roads and routes to and from a construction project.
However, this means that actors outside of the focal project needs to be
included in the CLS design and to allow for these actors to be able to utilize
and impact a CLS,

Acknowledgements

This project has received funding from the European Union's H2020 research and innovation programme and is part of the research programme JPI Urban Europe with project number 438.15.403 (MIMIC). This project is subsidised by the Brussels Capital Region - Innoviris and the European Union and receives funding from the Swedish Governmental Agency for Innovation Systems (Vinnova), the Austrian Federal Ministry for Transport, Innovation and Technology (BMVIT) in the framework of the research programme "Stadt der Zukunft" and the Austrian Federal Ministry of Science, Research and Economy (BMWFW) and The Research Council of Norway.